

**Cath Lab/Control Room**

|                             | Typical Finish                              | Finish Code     | Notes |
|-----------------------------|---------------------------------------------|-----------------|-------|
| <b>Walls</b>                | Epoxy Paint or Fiber Reinforced Epoxy Paint | P-1             | 1     |
| <b>Wall Protection</b>      | Sheet Goods                                 | W-Detail/Item D |       |
| <b>Floors</b>               | Terrazzo                                    | Terrazzo        | 1     |
| <b>Base</b>                 | Terrazzo Integral Base                      | Terrazzo        | 1     |
| <b>Doors</b>                | Plastic Laminate                            | PL-1 thru PL-7  | 1     |
| <b>Millwork:</b> Horizontal | Solid Surface                               | SS-1 or SS-2    | 1     |
| Vertical                    | Plastic Laminate                            | PL-1 thru PL-7  |       |
| <b>Ceiling</b>              | 5/8" Gypboard with Epoxy Paint              | P-1             | 1     |
| <b>Lighting</b>             | Per Architects' Specs                       |                 | 1     |

**Notes:**

1. Monolithic ceilings shall be no wider than 30" at any point without prior approval.
2. Appropriate finish material selected by Consultant to be approved by Tracy Smith Sare, Lead Project Manager, Architecture & Construction, 713.448.4002 or e-mail [tracy.smithsare@memorialhermann.org](mailto:tracy.smithsare@memorialhermann.org).

*Note: The finish type requirements outlined above are a general synopsis of the Texas Administrative Code, Department of State Health Services, Title 25, Chapter 133. This information is not to be used as a substitute for a thorough code/regulation research by the Consultant. Consultant shall be responsible for verification of all applicable codes and regulations governing finish types for their projects.* **Page 3.D.1**

**CT Room/Control Room/Simulator**

|                             | Typical Finish                                           | Finish Code                             | Notes |
|-----------------------------|----------------------------------------------------------|-----------------------------------------|-------|
| <b>Walls</b>                | Paint                                                    | P-1                                     | 1     |
| <b>Wall Protection</b>      | Sheet Goods                                              | W-Detail/Item D                         |       |
| <b>Floors</b>               | VCT or Seamless Vinyl                                    | VT-1 thru VT-3, SV-1, SV-3, SV-9, SV-11 | 1     |
| <b>Base</b>                 | Rubber Base                                              | B-1 thru B-3                            | 1     |
| <b>Doors</b>                | Plastic Laminate                                         | PL-1 thru PL-7                          | 1     |
| <b>Millwork:</b> Horizontal | Solid Surface or Plastic Laminate                        | SS-1 or SS-2 or PL-1 thru PL-7          | 1, 2  |
| Vertical                    | Plastic Laminate                                         | PL-1 thru PL-7                          |       |
| <b>Ceiling</b>              | Lay-in                                                   | CLG-2 thru CLG-4                        | 1     |
| <b>Lighting</b>             | 2x4 Parabolic Fluorescent, Compact Fluorescent Downlight | LTG-2, LTG-4                            | 1, 3  |

**Notes:**

1. Appropriate finish material selected by Consultant to be approved by Tracy Smith Sare, Lead Project Manager, Architecture & Construction, 713.448.4002 or e-mail [tracy.smithsare@memorialhermann.org](mailto:tracy.smithsare@memorialhermann.org).
2. Integral solid surface sink.
3. Special backlit ceiling panels permitted with approval by Tracy Smith Sare, Lead Project Manager, Architecture & Construction, 713.448.4002 or e-mail [tracy.smithsare@memorialhermann.org](mailto:tracy.smithsare@memorialhermann.org).

*Note: The finish type requirements outlined above are a general synopsis of the Texas Administrative Code, Department of State Health Services, Title 25, Chapter 133. This information is not to be used as a substitute for a thorough code/regulation research by the Consultant. Consultant shall be responsible for verification of all applicable codes and regulations governing finish types for their projects.* **Page 3.D.2**

## Consultation Room

|                             | Typical Finish                                         | Finish Code      | Notes |
|-----------------------------|--------------------------------------------------------|------------------|-------|
| <b>Walls</b>                | Paint                                                  | P-1              | 1     |
| <b>Wall Protection</b>      | N/A                                                    |                  |       |
| <b>Floors</b>               | Carpet Tile                                            | C-1 thru C-4     | 1     |
| <b>Base</b>                 | Rubber Base                                            | B-1 thru B-3     | 1     |
| <b>Doors</b>                | Plastic Laminate                                       | PL-1 thru PL-7   | 1     |
| <b>Millwork:</b> Horizontal | N/A                                                    |                  |       |
| Vertical                    |                                                        |                  |       |
| <b>Ceiling</b>              | Lay-in                                                 | CLG-2 thru CLG-4 | 1     |
| <b>Lighting</b>             | 2x4 Fluorescent Parabolic,<br>2x4 Indirect Fluorescent | LTG-1, LTG-2     | 1     |

**Notes:**

1. Appropriate finish material selected by Consultant to be approved by Tracy Smith Sare, Lead Project Manager, Architecture & Construction, 713.448.4002 or e-mail [tracy.smithsare@memorialhermann.org](mailto:tracy.smithsare@memorialhermann.org).

*Note: The finish type requirements outlined above are a general synopsis of the Texas Administrative Code, Department of State Health Services, Title 25, Chapter 133. This information is not to be used as a substitute for a thorough code/regulation research by the Consultant. Consultant shall be responsible for verification of all applicable codes and regulations governing finish types for their projects.* **Page 3.D.3**

## X-Ray and RF Room / Control Room

|                             | Typical Finish                                           | Finish Code                    | Notes |
|-----------------------------|----------------------------------------------------------|--------------------------------|-------|
| <b>Walls</b>                | Paint                                                    | P-1                            | 1     |
| <b>Wall Protection</b>      | Sheet Goods                                              | W-Detail/Item D                |       |
| <b>Floors</b>               | VCT                                                      | VT-1 thru VT-3                 | 1     |
| <b>Base</b>                 | Rubber Base                                              | B-1 thru B-3                   | 1     |
| <b>Doors</b>                | Plastic Laminate                                         | PL-1 thru PL-7                 | 1     |
| <b>Millwork:</b> Horizontal | Solid Surface or Plastic Laminate                        | SS-1 or SS-2 or PL-1 thru PL-7 | 1, 2  |
| Vertical                    | Plastic Laminate                                         | PL-1 thru PL-7                 |       |
| <b>Ceiling</b>              | Lay-in                                                   | CLG-1, CLG-2                   | 1     |
| <b>Lighting</b>             | 2x4 Parabolic Fluorescent, Compact Fluorescent Downlight | LTG-2, LTG-4                   | 1     |

**Notes:**

1. Appropriate finish material selected by Consultant to be approved by Tracy Smith Sare, Lead Project Manager, Architecture & Construction, 713.448.4002 or e-mail [tracy.smithsare@memorialhermann.org](mailto:tracy.smithsare@memorialhermann.org).
2. Integral solid surface sink, if applicable.

*Note: The finish type requirements outlined above are a general synopsis of the Texas Administrative Code, Department of State Health Services, Title 25, Chapter 133. This information is not to be used as a substitute for a thorough code/regulation research by the Consultant. Consultant shall be responsible for verification of all applicable codes and regulations governing finish types for their projects.* **Page 3.D.4**

## Dialysis/Chemotherapy Treatment Area

|                             | Typical Finish                                                                              | Finish Code             | Notes |
|-----------------------------|---------------------------------------------------------------------------------------------|-------------------------|-------|
| <b>Walls</b>                | Paint                                                                                       | P-1                     | 1     |
| <b>Wall Protection</b>      | Sheet Goods                                                                                 | W-Detail/Item D         |       |
| <b>Floors</b>               | Seamless Vinyl                                                                              | SV-1, SV-3, SV-9, SV-11 | 1     |
| <b>Base</b>                 | Seamless Vinyl Integral                                                                     | SV-1, SV-3, SV-9, SV-11 | 1     |
| <b>Doors</b>                | Plastic Laminate                                                                            | PL-1 thru PL-7          | 1     |
| <b>Millwork:</b> Horizontal | Solid Surface                                                                               | SS-1 or SS-2            | 1, 2  |
| Vertical                    | Plastic Laminate                                                                            | PL-1 thru PL-7          |       |
| <b>Ceiling</b>              | Lay-in                                                                                      | CLG-1, CLG-2            | 1     |
| <b>Lighting</b>             | 2x4 Parabolic Fluorescent,<br>2x4 Indirect Fluorescent,<br>Compact Fluorescent<br>Downlight | LTG-1, LTG-2, LTG-4     | 1     |

**Notes:**

1. Appropriate finish material selected by Consultant to be approved by Tracy Smith Sare, Lead Project Manager, Architecture & Construction, 713.448.4002 or e-mail [tracy.smithsare@memorialhermann.org](mailto:tracy.smithsare@memorialhermann.org).
2. Integral solid surface sink.

*Note: The finish type requirements outlined above are a general synopsis of the Texas Administrative Code, Department of State Health Services, Title 25, Chapter 133. This information is not to be used as a substitute for a thorough code/regulation research by the Consultant. Consultant shall be responsible for verification of all applicable codes and regulations governing finish types for their projects.* **Page 3.D.5**

## Dressing Room

|                              | Typical Finish                                          | Finish Code                       | Notes |
|------------------------------|---------------------------------------------------------|-----------------------------------|-------|
| <b>Walls</b>                 | Paint                                                   | P-1                               | 1     |
| <b>Wall Protection</b>       | N/A                                                     |                                   |       |
| <b>Floors</b>                | VCT or Carpet Tile                                      | VT-1 thru VT-3 or<br>C-1 thru C-4 | 1, 2  |
| <b>Base</b>                  | Rubber Base                                             | B-1 thru B-3                      | 1     |
| <b>Doors/Cubicle Curtain</b> | Plastic Laminate or Louvered<br>Door or Cubicle Curtain | PL-1 thru PL-7                    | 1, 3  |
| <b>Millwork:</b> Horizontal  | Solid Surface                                           | SS-1 or SS-2                      | 1     |
| Vertical                     | Plastic Laminate                                        | PL-1 thru PL-7                    |       |
| <b>Ceiling</b>               | Lay-in                                                  | CLG-1 thru CLG-3                  | 1     |
| <b>Lighting</b>              | Compact Fluorescent<br>Downlight                        | LTG-4                             |       |

### Notes:

1. Appropriate finish material selected by Consultant to be approved by Tracy Smith Sare, Lead Project Manager, Architecture & Construction, 713.448.4002 or e-mail [tracy.smithsare@memorialhermann.org](mailto:tracy.smithsare@memorialhermann.org).
2. See Part 2, 09650.1 for floor pattern options; Consultants may design new floor patterns with approval from Tracy Smith Sare, Lead Project Manager, Architecture & Construction, 713.448.4002 or e-mail [tracy.smithsare@memorialhermann.org](mailto:tracy.smithsare@memorialhermann.org).
3. See Section 18 for cubicle curtain specifications.

*Note: The finish type requirements outlined above are a general synopsis of the Texas Administrative Code, Department of State Health Services, Title 25, Chapter 133. This information is not to be used as a substitute for a thorough code/regulation research by the Consultant. Consultant shall be responsible for verification of all applicable codes and regulations governing finish types for their projects.* **Page 3.D.6**

**EEG/EKG Room**

|                             | Typical Finish            | Finish Code                                  | Notes |
|-----------------------------|---------------------------|----------------------------------------------|-------|
| <b>Walls</b>                | Paint                     | P-1                                          | 1     |
| <b>Wall Protection</b>      | Sheet Goods               | W-Detail/Item D                              |       |
| <b>Floors</b>               | VCT or Seamless Vinyl     | VT-1 thru VT-3 or SV-1,<br>SV-3, SV-9, SV-11 | 1, 2  |
| <b>Base</b>                 | Rubber Base               | B-1 thru B-3                                 | 1     |
| <b>Doors</b>                | Plastic Laminate          | PL-1 thru PL-7                               | 1     |
| <b>Millwork:</b> Horizontal | Solid Surface             | SS-1 or SS-2                                 | 1, 3  |
| Vertical                    | Plastic Laminate          | PL-1 thru PL-7                               |       |
| <b>Ceiling</b>              | Lay-in                    | CLG-1, CLG-2                                 | 1     |
| <b>Lighting</b>             | 2x4 Parabolic Fluorescent | LTG-2                                        | 1     |

**Notes:**

1. Appropriate finish material selected by Consultant to be approved by Tracy Smith Sare, Lead Project Manager, Architecture & Construction, 713.448.4002 or e-mail [tracy.smithsare@memorialhermann.org](mailto:tracy.smithsare@memorialhermann.org).
2. See Part 2, 09650.1 for floor pattern options; Consultants may design new floor patterns with approval from Tracy Smith Sare, Lead Project Manager, Architecture & Construction, 713.448.4002 or e-mail [tracy.smithsare@memorialhermann.org](mailto:tracy.smithsare@memorialhermann.org).
3. Integral solid surface sink.

*Note: The finish type requirements outlined above are a general synopsis of the Texas Administrative Code, Department of State Health Services, Title 25, Chapter 133. This information is not to be used as a substitute for a thorough code/regulation research by the Consultant. Consultant shall be responsible for verification of all applicable codes and regulations governing finish types for their projects.* **Page 3.D.7**

## Exam/Treatment Room

|                             | Typical Finish                                          | Finish Code                                  | Notes |
|-----------------------------|---------------------------------------------------------|----------------------------------------------|-------|
| <b>Walls</b>                | Paint                                                   | P-1                                          | 1     |
| <b>Wall Protection</b>      | Sheet Goods                                             | W-Detail/Item D                              |       |
| <b>Floors</b>               | VCT or Seamless Vinyl                                   | VT-1 thru VT-3 or SV-1,<br>SV-3, SV-9, SV-11 | 1, 2  |
| <b>Base</b>                 | Rubber Base                                             | B-1 thru B-3                                 | 1     |
| <b>Doors</b>                | Plastic Laminate                                        | PL-1 thru PL-7                               | 1     |
| <b>Millwork:</b> Horizontal | Solid Surface                                           | SS-1 or SS-2                                 | 1, 3  |
| Vertical                    | Plastic Laminate                                        | PL-1 thru PL-7                               |       |
| <b>Ceiling</b>              | Lay-in                                                  | CLG-1, CLG-2                                 | 1     |
| <b>Lighting</b>             | 2x4 Prismatic Fluorescent,<br>2x4 Parabolic Fluorescent | LTG-2, LTG-3                                 | 1     |

### Notes:

1. Appropriate finish material selected by Consultant to be approved by Tracy Smith Sare, Lead Project Manager, Architecture & Construction, 713.448.4002 or e-mail [tracy.smithsare@memorialhermann.org](mailto:tracy.smithsare@memorialhermann.org).
2. See Part 2, 09650.1 for floor pattern options; Consultants may design new floor patterns with approval from Tracy Smith Sare, Lead Project Manager, Architecture & Construction, 713.448.4002 or e-mail [tracy.smithsare@memorialhermann.org](mailto:tracy.smithsare@memorialhermann.org).
3. Integral solid surface sink.

*Note: The finish type requirements outlined above are a general synopsis of the Texas Administrative Code, Department of State Health Services, Title 25, Chapter 133. This information is not to be used as a substitute for a thorough code/regulation research by the Consultant. Consultant shall be responsible for verification of all applicable codes and regulations governing finish types for their projects.* **Page 3.D.8**



## Hot Lab / Injection Room

|                             | Typical Finish                                          | Finish Code             | Notes |
|-----------------------------|---------------------------------------------------------|-------------------------|-------|
| <b>Walls</b>                | Paint                                                   | P-1                     | 1     |
| <b>Wall Protection</b>      | N/A                                                     |                         |       |
| <b>Floors</b>               | Seamless Vinyl                                          | SV-1, SV-3, SV-9, SV-11 | 1, 2  |
| <b>Base</b>                 | Seamless Vinyl Integral                                 | SV-1, SV-3, SV-9, SV-11 | 1     |
| <b>Doors</b>                | Plastic Laminate                                        | PL-1 thru PL-7          | 1     |
| <b>Millwork:</b> Horizontal | Solid Surface                                           | SS-1 or SS-2            | 1, 3  |
| Vertical                    | Plastic Laminate                                        | PL-1 thru PL-7          |       |
| <b>Ceiling</b>              | Lay-in                                                  | CLG-1, CLG-2            | 1     |
| <b>Lighting</b>             | 2x4 Prismatic Fluorescent,<br>2x4 Parabolic Fluorescent | LTG-2, LTG-3            | 1     |

### Notes:

1. Appropriate finish material selected by Consultant to be approved by Tracy Smith Sare, Lead Project Manager, Architecture & Construction, 713.448.4002 or e-mail [tracy.smithsare@memorialhermann.org](mailto:tracy.smithsare@memorialhermann.org).
2. See Part 2, 0960 for floor pattern options; Consultants may design new floor patterns with approval from Tracy Smith Sare, Lead Project Manager, Architecture & Construction, 713.448.4002 or e-mail [tracy.smithsare@memorialhermann.org](mailto:tracy.smithsare@memorialhermann.org).
3. Integral solid surface sink.

*Note: The finish type requirements outlined above are a general synopsis of the Texas Administrative Code, Department of State Health Services, Title 25, Chapter 133. This information is not to be used as a substitute for a thorough code/regulation research by the Consultant. Consultant shall be responsible for verification of all applicable codes and regulations governing finish types for their projects.* **Page 3.D.9**

**Labs**

|                             | Typical Finish            | Finish Code              | Notes |
|-----------------------------|---------------------------|--------------------------|-------|
| <b>Walls</b>                | Paint                     | P-1                      | 1     |
| <b>Wall Protection</b>      | Sheet Goods               | W-1, W-2, Section/Item D |       |
| <b>Floors</b>               | Seamless Vinyl            | SV-1, SV-3, SV-9, SV-11  | 1     |
| <b>Base</b>                 | Seamless Vinyl Integral   | SV-1, SV-3, SV-9, SV-11  | 1     |
| <b>Doors</b>                | Plastic Laminate          | PL-1 thru PL-8           | 1     |
| <b>Millwork:</b> Horizontal | Solid Surface             | SS-1 or SS-2             | 1     |
| Vertical                    | Plastic Laminate          | PL-1 thru PL-8           |       |
| <b>Ceiling</b>              | Lay-in                    | CLG-6                    |       |
| <b>Lighting</b>             | 2x4 Prismatic Fluorescent | LTG-3                    |       |

**Notes:**

1. Appropriate finish material selected by Consultant to be approved by Tracy Smith Sare, Lead Project Manager, Architecture & Construction, 713.448.4002 or e-mail [tracy.smithsare@memorialhermann.org](mailto:tracy.smithsare@memorialhermann.org).

*Note: The finish type requirements outlined above are a general synopsis of the Texas Administrative Code, Department of State Health Services, Title 25, Chapter 133. This information is not to be used as a substitute for a thorough code/regulation research by the Consultant. Consultant shall be responsible for verification of all applicable codes and regulations governing finish types for their projects.* **Page 3.D.10**

**Linear Accelerator/Linear Accelerator Simulator/Gamma Camera/  
Gamma Knife/Control Room**

|                             | Typical Finish                                | Finish Code            | Notes |
|-----------------------------|-----------------------------------------------|------------------------|-------|
| <b>Walls</b>                | Paint                                         | P-1                    | 1     |
| <b>Wall Protection</b>      | Sheet Goods and/or Upper and Lower Crash Rail | W-Detail/Items B and D |       |
| <b>Floors</b>               | VCT                                           | VT-1, VT-2             | 1, 2  |
| <b>Base</b>                 | Rubber Base                                   | B-1 thru B-3           | 1     |
| <b>Doors</b>                | Plastic Laminate                              | PL-1 thru PL-7         | 1     |
| <b>Millwork:</b> Horizontal | Solid Surface                                 | SS-1 or SS-2           | 1     |
| Vertical                    | Plastic Laminate                              | PL-1 thru PL-7         | 1     |
| <b>Ceiling</b>              | Lay-in                                        | CLG-6                  | 1     |
| <b>Lighting</b>             | 2x4 Parabolic Fluorescent                     | LTG-2                  | 1     |

**Notes:**

1. Appropriate finish material selected by Consultant to be approved by Tracy Smith Sare, Lead Project Manager, Architecture & Construction, 713.448.4002 or e-mail [tracy.smithsare@memorialhermann.org](mailto:tracy.smithsare@memorialhermann.org).
2. See Part 2, 90650.1 for floor pattern options; Consultants may design new floor patterns with approval from Tracy Smith Sare, Lead Project Manager, Architecture & Construction, 713.448.4002 or e-mail [tracy.smithsare@memorialhermann.org](mailto:tracy.smithsare@memorialhermann.org).

*Note: The finish type requirements outlined above are a general synopsis of the Texas Administrative Code, Department of State Health Services, Title 25, Chapter 133. This information is not to be used as a substitute for a thorough code/regulation research by the Consultant. Consultant shall be responsible for verification of all applicable codes and regulations governing finish types for their projects.* **Page 3.D.11**

**MRI Room**

|                             | Typical Finish                                                | Finish Code     | Notes |
|-----------------------------|---------------------------------------------------------------|-----------------|-------|
| <b>Walls</b>                | Paint                                                         | P-1             | 1     |
| <b>Wall Protection</b>      | Sheet Goods                                                   | W-Detail/Item D |       |
| <b>Floors</b>               | Static Dissipative Tile                                       | SDT-1, SDT-2    | 1, 2  |
| <b>Base</b>                 | Rubber Base                                                   | B-1 thru B-3    | 1     |
| <b>Doors</b>                | Plastic Laminate                                              | PL-1 thru PL-7  | 1     |
| <b>Millwork:</b> Horizontal | Plastic Laminate                                              | PL-1 thru PL-7  | 1     |
| Vertical                    | Plastic Laminate                                              | PL-1 thru PL-7  |       |
| <b>Ceiling</b>              | Lay-in (Non-Ferrous Grid)                                     | CLG-4, CLG-5    | 1     |
| <b>Lighting</b>             | 2x4 Indirect Fluorescent,<br>Compact Fluorescent<br>Downlight | LTG-1, LTG-4    | 3     |

**Notes:**

1. Appropriate finish material selected by Consultant to be approved by Tracy Smith Sare, Lead Project Manager, Architecture & Construction, 713.448.4002 or e-mail [tracy.smithsare@memorialhermann.org](mailto:tracy.smithsare@memorialhermann.org).
2. Use anti-static floor tile unless approved otherwise by equipment vendor.
3. Special backlit ceiling panels permitted with approval by Tracy Smith Sare, Lead Project Manager, Architecture & Construction, 713.448.4002 or e-mail [tracy.smithsare@memorialhermann.org](mailto:tracy.smithsare@memorialhermann.org).

*Note: The finish type requirements outlined above are a general synopsis of the Texas Administrative Code, Department of State Health Services, Title 25, Chapter 133. This information is not to be used as a substitute for a thorough code/regulation research by the Consultant. Consultant shall be responsible for verification of all applicable codes and regulations governing finish types for their projects.* **Page 3.D.12**

## Mammography/Stereotactic/Bone Density/Ultrasound Room

|                             | Typical Finish                                                 | Finish Code                      | Notes |
|-----------------------------|----------------------------------------------------------------|----------------------------------|-------|
| <b>Walls</b>                | Paint                                                          | P-1                              | 1     |
| <b>Wall Protection</b>      | N/A                                                            |                                  |       |
| <b>Floors</b>               | VCT or Seamless Vinyl                                          | VT-1 thru VT-3 or SV-5 thru SV-8 | 1, 2  |
| <b>Base</b>                 | Rubber Base                                                    | B-1 thru B-3                     | 1     |
| <b>Doors</b>                | Plastic Laminate                                               | PL-1 thru PL-7                   | 1     |
| <b>Millwork:</b> Horizontal | Solid Surface                                                  | SS-1 or SS-2                     | 1, 3  |
| Vertical                    | Plastic Laminate                                               | PL-1 thru PL-7                   |       |
| <b>Ceiling</b>              | Lay-in                                                         | CLG-2                            |       |
| <b>Lighting</b>             | 2x4 Parabolic Fluorescent,<br>Compact Fluorescent<br>Downlight | LTG-2, LTG-4                     | 1     |

**Notes:**

1. Appropriate finish material selected by Consultant to be approved by Tracy Smith Sare, Lead Project Manager, Architecture & Construction, 713.448.4002 or e-mail [tracy.smithsare@memorialhermann.org](mailto:tracy.smithsare@memorialhermann.org).
2. See Part 2, 90650.1 for floor pattern options; Consultants may design new floor patterns with approval from Tracy Smith Sare, Lead Project Manager, Architecture & Construction, 713.448.4002 or e-mail [tracy.smithsare@memorialhermann.org](mailto:tracy.smithsare@memorialhermann.org).
3. Integral solid surface sink.

*Note: The finish type requirements outlined above are a general synopsis of the Texas Administrative Code, Department of State Health Services, Title 25, Chapter 133. This information is not to be used as a substitute for a thorough code/regulation research by the Consultant. Consultant shall be responsible for verification of all applicable codes and regulations governing finish types for their projects.* **Page 3.D.13**

## Medication Room

|                             | Typical Finish            | Finish Code                                | Notes |
|-----------------------------|---------------------------|--------------------------------------------|-------|
| <b>Walls</b>                | Epoxy Paint               | P-1                                        | 1     |
| <b>Wall Protection</b>      | Sheet Goods               | W-Detail/Item D                            |       |
| <b>Floors</b>               | VCT or Seamless Vinyl     | VT-1 thru VT-3, SV-1, SV-3,<br>SV-9, SV-11 | 1     |
| <b>Base</b>                 | Rubber Base               | B-1 thru B-3                               | 1     |
| <b>Doors</b>                | Plastic Laminate          | PL-1 thru PL-7                             | 1     |
| <b>Millwork:</b> Horizontal | Solid Surface             | SS-1 or SS-2                               | 1, 2  |
| Vertical                    | Plastic Laminate          | PL-1 thru PL-7                             |       |
| <b>Ceiling</b>              | Lay-in                    | CLG-1, CLG-2                               | 1     |
| <b>Lighting</b>             | 2x4 Prismatic Fluorescent | LTG-3                                      |       |

**Notes:**

1. Appropriate finish material selected by Consultant to be approved by Tracy Smith Sare, Lead Project Manager, Architecture & Construction, 713.448.4002 or e-mail [tracy.smithsare@memorialhermann.org](mailto:tracy.smithsare@memorialhermann.org).
2. Integral solid surface sink.

*Note: The finish type requirements outlined above are a general synopsis of the Texas Administrative Code, Department of State Health Services, Title 25, Chapter 133. This information is not to be used as a substitute for a thorough code/regulation research by the Consultant. Consultant shall be responsible for verification of all applicable codes and regulations governing finish types for their projects.* **Page 3.D.14**

## Morgue

|                             | Typical Finish                                          | Finish Code                       | Notes |
|-----------------------------|---------------------------------------------------------|-----------------------------------|-------|
| <b>Walls</b>                | Epoxy Paint                                             | P-1                               | 1     |
| <b>Wall Protection</b>      | Sheet Goods                                             | W Detail / Section D              |       |
| <b>Floors</b>               | Seamless Vinyl                                          | SV-1, SV-3, SV-9, SV-11           | 1     |
| <b>Base</b>                 | Seamless Vinyl Integral                                 | SV-1, SV-3, SV-9, SV-11           | 1     |
| <b>Doors</b>                | Plastic Laminate                                        | PL-1 thru PL-7                    | 1     |
| <b>Millwork:</b> Horizontal | Stainless Steel or Solid Surface                        | Stainless Steel or SS-1 or SS-2   | 1     |
| Vertical                    | Stainless Steel or Plastic Laminate                     | Stainless Steel or PL-1 thru PL-7 | 1     |
| <b>Ceiling</b>              | 5/8" Gypsum, Epoxy Paint                                | P-1                               | 1     |
| <b>Lighting</b>             | 2x4 Prismatic Fluorescent,<br>2x4 Parabolic Fluorescent | LTG-2, LTG-3                      | 1     |

### Notes:

1. Appropriate finish material selected by Consultant to be approved by Tracy Smith Sare, Lead Project Manager, Architecture & Construction, 713.448.4002 or e-mail [tracy.smithsare@memorialhermann.org](mailto:tracy.smithsare@memorialhermann.org).
2. Monolithic ceilings shall be no wider than 30" at any point without prior approval.

*Note: The finish type requirements outlined above are a general synopsis of the Texas Administrative Code, Department of State Health Services, Title 25, Chapter 133. This information is not to be used as a substitute for a thorough code/regulation research by the Consultant. Consultant shall be responsible for verification of all applicable codes and regulations governing finish types for their projects.* **Page 3.D.15**

**Nourishment Station**

|                             | Typical Finish            | Finish Code                             | Notes |
|-----------------------------|---------------------------|-----------------------------------------|-------|
| <b>Walls</b>                | Epoxy Paint               | P-1                                     | 1     |
| <b>Wall Protection</b>      | Sheet Goods               | W-Detail/Item D                         |       |
| <b>Floors</b>               | VCT or Seamless Vinyl     | VT-1 thru VT-3, SV-1, SV-3, SV-9, SV-11 | 1     |
| <b>Base</b>                 | Rubber Base               | B-1 thru B-3                            | 1     |
| <b>Doors</b>                | Plastic Laminate          | PL-1 thru PL-7                          | 1     |
| <b>Millwork:</b> Horizontal | Solid Surface             | SS-1 or SS-2                            | 1, 2  |
| Vertical                    | Plastic Laminate          | PL-1 thru PL-7                          |       |
| <b>Ceiling</b>              | Lay-in                    | CLG-1, CLG-2                            | 1     |
| <b>Lighting</b>             | 2x4 Prismatic Fluorescent | LTG-3                                   |       |

**Notes:**

1. Appropriate finish material selected by Consultant to be approved by Tracy Smith Sare, Lead Project Manager, Architecture & Construction, 713.448.4002 or e-mail [tracy.smithsare@memorialhermann.org](mailto:tracy.smithsare@memorialhermann.org).
2. Integral solid surface sink.

*Note: The finish type requirements outlined above are a general synopsis of the Texas Administrative Code, Department of State Health Services, Title 25, Chapter 133. This information is not to be used as a substitute for a thorough code/regulation research by the Consultant. Consultant shall be responsible for verification of all applicable codes and regulations governing finish types for their projects.* **Page 3.D.16**



## Nuclear Med Room

|                             | Typical Finish                                          | Finish Code             | Notes |
|-----------------------------|---------------------------------------------------------|-------------------------|-------|
| <b>Walls</b>                | Paint                                                   | P-1                     | 1     |
| <b>Wall Protection</b>      | Sheet Goods                                             | W-Detail/Item D         |       |
| <b>Floors</b>               | Seamless Vinyl                                          | SV-1, SV-3, SV-9, SV-11 | 1     |
| <b>Base</b>                 | Seamless Vinyl Integral                                 | SV-1, SV-3, SV-9, SV-11 | 1     |
| <b>Doors</b>                | Plastic Laminate                                        | PL-1 thru PL-7          | 1     |
| <b>Millwork:</b> Horizontal | Solid Surface                                           | SS-1 or SS-2            | 1, 2  |
| Vertical                    | Plastic Laminate                                        | PL-1 thru PL-7          |       |
| <b>Ceiling</b>              | Lay-in                                                  | CLG-1 or CLG-2          | 1     |
| <b>Lighting</b>             | 2x4 Prismatic Fluorescent,<br>2x4 Parabolic Fluorescent | LTG-2, LTG-3            | 1     |

**Notes:**

1. Appropriate finish material selected by Consultant to be approved by Tracy Smith Sare, Lead Project Manager, Architecture & Construction, 713.448.4002 or e-mail [tracy.smithsare@memorialhermann.org](mailto:tracy.smithsare@memorialhermann.org).
2. Integral solid surface sink.

*Note: The finish type requirements outlined above are a general synopsis of the Texas Administrative Code, Department of State Health Services, Title 25, Chapter 133. This information is not to be used as a substitute for a thorough code/regulation research by the Consultant. Consultant shall be responsible for verification of all applicable codes and regulations governing finish types for their projects.* **Page 3.D.17**

**Nursery: NICU**

|                             | Typical Finish                                                                                                  | Finish Code                                                      | Notes |
|-----------------------------|-----------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------|-------|
| <b>Walls</b>                | Paint                                                                                                           | P-1                                                              | 1     |
| <b>Wall Protection</b>      | Sheet Goods                                                                                                     | W-1, W-2, W-Detail/Item D                                        | 1     |
| <b>Floors</b>               | Seamless Vinyl or Carpet Tile                                                                                   | SV-1, SV-3 thru SV-9, SV-11<br>or C-3, C-4, C-6, C-7<br>thru C-9 | 1, 2  |
| <b>Base</b>                 | Seamless Vinyl Integral or<br>Rubber Base                                                                       | SV-1, SV-3 thru SV-9, SV-11<br>or B-1 thru B-3                   | 1     |
| <b>Doors</b>                | Plastic Laminate                                                                                                | PL-1 thru PL-7                                                   | 1     |
| <b>Millwork:</b> Horizontal | Solid Surface                                                                                                   | SS-1 or SS-2                                                     | 1, 3  |
| Vertical                    | Plastic Laminate                                                                                                | PL-1 thru PL-7                                                   |       |
| <b>Ceiling</b>              | Lay-in                                                                                                          | CLG-4, CLG-5                                                     | 1     |
| <b>Lighting</b>             | 2x4 Indirect Fluorescent,<br>Indirect Coved Fluorescent<br>(Gypboard or Pre-fab), Linear<br>Pendant Fluorescent | LTG-1                                                            | 1     |

**Notes:**

1. Appropriate finish material selected by Consultant to be approved by Tracy Smith Sare, Lead Project Manager, Architecture & Construction, 713.448.4002 or e-mail [tracy.smithsare@memorialhermann.org](mailto:tracy.smithsare@memorialhermann.org).
2. Consultant may design floor pattern with approval from Tracy Smith Sare, Lead Project Manager, Architecture & Construction, 713.448.4002 or e-mail [tracy.smithsare@memorialhermann.org](mailto:tracy.smithsare@memorialhermann.org).
3. Integral solid surface sink or wall mounted lavatory.

*Note: The finish type requirements outlined above are a general synopsis of the Texas Administrative Code, Department of State Health Services, Title 25, Chapter 133. This information is not to be used as a substitute for a thorough code/regulation research by the Consultant. Consultant shall be responsible for verification of all applicable codes and regulations governing finish types for their projects.* **Page 3.D.18**

**Nursery: Well Baby**

|                             | Typical Finish                                         | Finish Code                                          | Notes |
|-----------------------------|--------------------------------------------------------|------------------------------------------------------|-------|
| <b>Walls</b>                | Paint                                                  | P-1                                                  | 1     |
| <b>Wall Protection</b>      | Sheet Goods                                            | W-1, W-2, W-Detail/Item D                            |       |
| <b>Floors</b>               | Seamless Vinyl                                         | SV-1, SV-3, SV-5 thru SV-9,<br>SV-11                 | 1, 2  |
| <b>Base</b>                 | Seamless Vinyl Integral or<br>Rubber Base              | SV-1, SV-3, SV-5 thru SV-9,<br>SV-11 or B-1 thru B-3 | 1     |
| <b>Doors</b>                | Plastic Laminate                                       | PL-1 thru PL-7                                       | 1     |
| <b>Millwork:</b> Horizontal | Solid Surface                                          | SS-1 or SS-2                                         | 1,3   |
| Vertical                    | Plastic Laminate                                       | PL-1 thru PL-7                                       |       |
| <b>Ceiling</b>              | Lay-in                                                 | CLG-4, CLG-5                                         | 1     |
| <b>Lighting</b>             | 2x4 Indirect Fluorescent,<br>2x4 Parabolic Fluorescent | LTG-1, LTG-2                                         | 1     |

**Notes:**

1. Appropriate finish material selected by Consultant to be approved by Tracy Smith Sare, Lead Project Manager, Architecture & Construction, 713.448.4002 or e-mail [tracy.smithsare@memorialhermann.org](mailto:tracy.smithsare@memorialhermann.org).
2. Consultant may design floor pattern with approval from Tracy Smith Sare, Lead Project Manager, Architecture & Construction, 713.448.4002 or e-mail [tracy.smithsare@memorialhermann.org](mailto:tracy.smithsare@memorialhermann.org).
3. Integral solid surface sink or wall mounted lavatory.

*Note: The finish type requirements outlined above are a general synopsis of the Texas Administrative Code, Department of State Health Services, Title 25, Chapter 133. This information is not to be used as a substitute for a thorough code/regulation research by the Consultant. Consultant shall be responsible for verification of all applicable codes and regulations governing finish types for their projects.* **Page 3.D.19**

## Operating Suite: Operating Room

|                             | Typical Finish                              | Finish Code               | Notes |
|-----------------------------|---------------------------------------------|---------------------------|-------|
| <b>Walls</b>                | Epoxy Paint or Fiber Reinforced Epoxy Paint | P-1                       | 1     |
| <b>Wall Protection</b>      | Sheet Goods                                 | W-1, W-2, W-Detail/Item D | 1     |
| <b>Floors</b>               | Terrazzo                                    | Terrazzo                  | 1     |
| <b>Base</b>                 | Terrazzo Integral Cove                      | Terrazzo                  | 1     |
| <b>Doors</b>                | Plastic Laminate                            | PL-1 thru PL-7            | 1, 2  |
| <b>Millwork:</b> Horizontal | Solid Surface                               | SS-1 or SS-2              | 1     |
| Vertical                    | Plastic Laminate                            | PL-1 thru PL-7            |       |
| <b>Ceiling</b>              | 5/8" Gypboard with Epoxy Paint              | P-1                       | 1     |
| <b>Lighting</b>             | Per Architects' Specs                       |                           | 1     |

**Notes:**

1. Appropriate finish material selected by Consultant to be approved by Tracy Smith Sare, Lead Project Manager, Architecture & Construction, 713.448.4002 or e-mail [tracy.smithsare@memorialhermann.org](mailto:tracy.smithsare@memorialhermann.org).
2. Provide stainless steel armor protection.
3. Monolithic ceilings shall be no wider than 30" at any point without prior approval.

*Note: The finish type requirements outlined above are a general synopsis of the Texas Administrative Code, Department of State Health Services, Title 25, Chapter 133. This information is not to be used as a substitute for a thorough code/regulation research by the Consultant. Consultant shall be responsible for verification of all applicable codes and regulations governing finish types for their projects.* **Page 3.D.20**

**Operating Suite: Caesarean Section (C-Section) Room**

|                             | Typical Finish                              | Finish Code               | Notes |
|-----------------------------|---------------------------------------------|---------------------------|-------|
| <b>Walls</b>                | Epoxy Paint or Fiber Reinforced Epoxy Paint | P-1                       | 1     |
| <b>Wall Protection</b>      | Sheet Goods                                 | W-1, W-2, W-Detail/Item D | 1     |
| <b>Floors</b>               | Terrazzo                                    |                           | 1     |
| <b>Base</b>                 | Integral Terrazzo Base                      |                           | 1     |
| <b>Doors</b>                | Plastic Laminate                            | PL-1 thru PL-7            | 1, 2  |
| <b>Millwork:</b> Horizontal | Solid Surface                               | SS-1 or SS-2              | 1     |
| Vertical                    | Plastic Laminate                            | PL-1 thru PL-7            |       |
| <b>Ceiling</b>              | 5/8" Gypboard with Epoxy Paint              | P-1                       | 1     |
| <b>Lighting</b>             | Per Architects' Specs                       |                           | 1     |

**Notes:**

1. Appropriate finish material selected by Consultant to be approved by Tracy Smith Sare, Lead Project Manager, Architecture & Construction, 713.448.4002 or e-mail [tracy.smithsare@memorialhermann.org](mailto:tracy.smithsare@memorialhermann.org).
2. Provide stainless steel armor protection.
3. Monolithic ceilings shall be no wider than 30" at any point without prior approval.

*Note: The finish type requirements outlined above are a general synopsis of the Texas Administrative Code, Department of State Health Services, Title 25, Chapter 133. This information is not to be used as a substitute for a thorough code/regulation research by the Consultant. Consultant shall be responsible for verification of all applicable codes and regulations governing finish types for their projects.* **Page 3.D.21**

## Operating Suite: Scrub Area

|                             | Typical Finish                 | Finish Code               | Notes |
|-----------------------------|--------------------------------|---------------------------|-------|
| <b>Walls</b>                | Epoxy Paint                    | P-1                       | 1     |
| <b>Wall Protection</b>      | Sheet Goods                    | W-1, W-2, W-Detail/Item D | 1     |
| <b>Floors</b>               | Seamless Vinyl                 | SV-1, SV-3, SV-9, SV-11   | 1     |
| <b>Base</b>                 | Seamless Vinyl Integral Cove   | SV-1, SV-3, SV-9, SV-11   | 1     |
| <b>Doors</b>                | Plastic Laminate               | PL-1 thru PL-7            | 1     |
| <b>Millwork:</b> Horizontal | N/A                            |                           |       |
| Vertical                    | N/A                            |                           |       |
| <b>Ceiling</b>              | 5/8" Gypboard with Epoxy Paint | P-1                       | 1     |
| <b>Lighting</b>             | Per Architects' Specs          |                           | 1     |

**Notes:**

1. Appropriate finish material selected by Consultant to be approved by Tracy Smith Sare, Lead Project Manager, Architecture & Construction, 713.448.4002 or e-mail [tracy.smithsare@memorialhermann.org](mailto:tracy.smithsare@memorialhermann.org).
2. Monolithic ceilings shall be no wider than 30" at any point without prior approval.

*Note: The finish type requirements outlined above are a general synopsis of the Texas Administrative Code, Department of State Health Services, Title 25, Chapter 133. This information is not to be used as a substitute for a thorough code/regulation research by the Consultant. Consultant shall be responsible for verification of all applicable codes and regulations governing finish types for their projects.* **Page 3.D.22**

## Phlebotomy Station/Room

|                             | Typical Finish            | Finish Code               | Notes |
|-----------------------------|---------------------------|---------------------------|-------|
| <b>Walls</b>                | Paint                     | P-1                       | 1     |
| <b>Wall Protection</b>      | Sheet Goods               | W-1, W-2, W-Detail/Item D | 1     |
| <b>Floors</b>               | Seamless Vinyl            | SV-1, SV-3, SV-9, SV-11   | 1     |
| <b>Base</b>                 | Seamless Vinyl Integral   | SV-1, SV-3, SV-9, SV-11   | 1     |
| <b>Doors</b>                | Plastic Laminate          | PL-1 thru PL-7            | 1     |
| <b>Millwork:</b> Horizontal | Solid Surface             | SS-1 or SS-2              | 1, 2  |
| Vertical                    | Plastic Laminate          | PL-1 thru PL-7            |       |
| <b>Ceiling</b>              | Lay-in                    | CLG-1, CLG-2              | 1     |
| <b>Lighting</b>             | 2x4 Parabolic Fluorescent | LTG-2                     | 1     |

**Notes:**

1. Appropriate finish material selected by Consultant to be approved by Tracy Smith Sare, Lead Project Manager, Architecture & Construction, 713.448.4002 or e-mail [tracy.smithsare@memorialhermann.org](mailto:tracy.smithsare@memorialhermann.org).
2. Integral solid surface sink.

*Note: The finish type requirements outlined above are a general synopsis of the Texas Administrative Code, Department of State Health Services, Title 25, Chapter 133. This information is not to be used as a substitute for a thorough code/regulation research by the Consultant. Consultant shall be responsible for verification of all applicable codes and regulations governing finish types for their projects.* **Page 3.D.23**

**Pre-Op/PACU/Observation/Recovery**

|                             | Typical Finish                                                                                                               | Finish Code                               | Notes |
|-----------------------------|------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------|-------|
| <b>Walls</b>                | Paint                                                                                                                        | P-1                                       | 1     |
| <b>Wall Protection</b>      | Sheet Goods                                                                                                                  | W-1, W-2, W-Detail/Item D                 | 1     |
| <b>Floors</b>               | VCT or Seamless Vinyl                                                                                                        | VT-1 thru VT-3 or SV-1, SV-3, SV-9, SV-11 | 1, 2  |
| <b>Base</b>                 | Rubber Base, Seamless Vinyl<br>Integral                                                                                      | B-1 thru B-3 or SV-1, SV-3, SV-9, SV-11   | 1     |
| <b>Doors</b>                | Plastic Laminate or Glass                                                                                                    | PL-1 thru PL-7 or Glass                   | 1     |
| <b>Millwork:</b> Horizontal | Solid Surface or Plastic Laminate                                                                                            | SS-1 or SS-2 or PL-1 thru PL-7            | 3     |
| Vertical                    | Plastic Laminate                                                                                                             | PL-1 thru PL-7                            |       |
| <b>Ceiling</b>              | Lay-in                                                                                                                       | CLG-1, CLG-2                              | 1     |
| <b>Lighting</b>             | 2x4 Prismatic Fluorescent,<br>2x4 Parabolic Fluorescent,<br>2x4 Multifunction Patient Light or Wall Mounted<br>Overbed Light | LTG-2, LTG-2, LTG-7 or LTG-8              | 1     |

**Notes:**

1. Appropriate finish material selected by Consultant to be approved by Tracy Smith Sare, Lead Project Manager, Architecture & Construction, 713.448.4002 or e-mail [tracy.smithsare@memorialhermann.org](mailto:tracy.smithsare@memorialhermann.org).
2. See Part 2, 09650.1 for floor pattern options; Consultants may design new floor patterns with approval from Tracy Smith Sare, Lead Project Manager, Architecture & Construction, 713.448.4002 or e-mail [tracy.smithsare@memorialhermann.org](mailto:tracy.smithsare@memorialhermann.org).
3. Integral solid surface sink.

*Note: The finish type requirements outlined above are a general synopsis of the Texas Administrative Code, Department of State Health Services, Title 25, Chapter 133. This information is not to be used as a substitute for a thorough code/regulation research by the Consultant. Consultant shall be responsible for verification of all applicable codes and regulations governing finish types for their projects.* **Page 3.D.24**



## Sterile Corridor

|                             | Typical Finish                                         | Finish Code               | Notes |
|-----------------------------|--------------------------------------------------------|---------------------------|-------|
| <b>Walls</b>                | Paint                                                  | P-1                       | 1     |
| <b>Wall Protection</b>      | Upper and Lower Crash Rail,                            | W-1, W-2, W-Detail/Item B | 1     |
| <b>Floors</b>               | Seamless Vinyl                                         | SV-1, SV-3, SV-9, SV-11   | 1     |
| <b>Base</b>                 | Seamless Vinyl Integral                                | SV-1, SV-3, SV-9, SV-11   | 1     |
| <b>Doors</b>                | Plastic Laminate                                       | PL-1 thru PL-7            | 1, 2  |
| <b>Millwork:</b> Horizontal | Solid Surface                                          | SS-1 or SS-2              | 1     |
| Vertical                    | Plastic Laminate                                       | PL-1 thru PL-7            | 1     |
| <b>Ceiling</b>              | 5/8" Gypboard, Epoxy Paint                             | P-1                       | 1     |
| <b>Lighting</b>             | 2x4 Parabolic Fluorescent,<br>2x4 Indirect Fluorescent | LTG-1, LTG-2              | 1     |

### Notes:

1. Appropriate finish material selected by Consultant to be approved by Tracy Smith Sare, Lead Project Manager, Architecture & Construction, 713.448.4002 or e-mail [tracy.smithsare@memorialhermann.org](mailto:tracy.smithsare@memorialhermann.org).
2. Provide stainless steel corner protection.
3. Monolithic ceilings shall be no wider than 30" at any point without prior approval.

*Note: The finish type requirements outlined above are a general synopsis of the Texas Administrative Code, Department of State Health Services, Title 25, Chapter 133. This information is not to be used as a substitute for a thorough code/regulation research by the Consultant. Consultant shall be responsible for verification of all applicable codes and regulations governing finish types for their projects.* **Page 3.D.25**

**Trauma Room/ER Exam Room**

|                             | Typical Finish                                         | Finish Code               | Notes |
|-----------------------------|--------------------------------------------------------|---------------------------|-------|
| <b>Walls</b>                | Paint                                                  | P-1                       | 1     |
| <b>Wall Protection</b>      | Sheet Goods                                            | W-1, W-2, W-Detail/Item D |       |
| <b>Floors</b>               | Seamless Vinyl                                         | SV-1, SV-3, SV-9, SV-11   | 1     |
| <b>Base</b>                 | Seamless Vinyl Integral                                | SV-1, SV-3, SV-9, SV-11   | 1     |
| <b>Doors</b>                | Plastic Laminate                                       | PL-1 thru PL-7            | 1     |
| <b>Millwork:</b> Horizontal | Solid Surface                                          | SS-1 or SS-2              | 1, 2  |
| Vertical                    | Plastic Laminate                                       | PL-1 thru PL-7            | 1, 2  |
| <b>Ceiling</b>              | Lay-in                                                 | CLG-1 or CLG 2            | 1     |
| <b>Lighting</b>             | 2x4 Parabolic Fluorescent<br>2x4 Prismatic Fluorescent | LTG-2, LTG-3              | 1     |

**Notes:**

1. Appropriate finish material selected by Consultant to be approved by Tracy Smith Sare, Lead Project Manager, Architecture & Construction, 713.448.4002 or e-mail [tracy.smithsare@memorialhermann.org](mailto:tracy.smithsare@memorialhermann.org).
2. Integral solid surface sink.

*Note: The finish type requirements outlined above are a general synopsis of the Texas Administrative Code, Department of State Health Services, Title 25, Chapter 133. This information is not to be used as a substitute for a thorough code/regulation research by the Consultant. Consultant shall be responsible for verification of all applicable codes and regulations governing finish types for their projects.* **Page 3.D.26**